



STRUCTURAL SCHEDULE

(BA)	- 8431BR 4 X 3 X 1/2 X 16GA ANGLE (8.9)	- FLOOR BASE ANGLE
(BC)	- 14251BR 4 X 1/8 X 2 7/8 X 16GA CHANNEL (9.9)	- FLOOR BASE CHANNEL
(BD)	- C421BR 4 X 2 X 1/2 X 16GA ZEE (8.9)	- 4" COLUMN
(BE)	- C251BR 6 X 2 1/2 X 1/2 X 16GA ZEE (11.9)	- 6" COLUMN
(BF)	- C421BR 4 X 2 X 1/2 X 16GA ZEE (8.9)	- DOOR HEAD
(BG)	- C4251BR 4 X 1/8 X 2 7/8 X 16GA CHANNEL (9.9)	- DOOR JAMB
(BH)	- E4431BR/0 3 X 6 X 4 X 16GA STRUT (13.9)	- EAVE CHANNEL
(BI)	- AS MANUFACTURED	- EAVE STRUT
(BJ)	- C421BR 4 X 2 X 1/2 X 16GA ZEE (8.9)	- FLOOR CLIP
(BK)	- B421BR 4 X 2 X 1/2 X 16GA ANGLE (5.9)	- GIRT
(BL)	- C421BR 4 X 2 X 1/2 X 16GA ZEE (8.9)	- DOOR HEAD REINFORCEMENT
(BM)	- C251BR 6 X 2 1/2 X 1/2 X 16GA ZEE (11.9)	- MULLION
(BN)	- C821BR 8 X 2 X 1/2 X 16GA ZEE (15.9)	- JACK RAFTER
(BO)	- B421BR 4 X 2 X 1/2 X 16GA ANGLE (5.9)	- MINN CLIP
(BP)	- R4251BR 2 1/2 X 8 X 2 1/2 X 1/2 X 16GA ZEE (9.9)	- ROOF PURLIN
(BQ)	- Z6251BR 2 1/2 X 8 X 2 1/2 X 1/2 X 16GA ZEE (11.9)	- ROOF PURLIN
(BR)	- B421BR 4 X 2 X 1/2 X 16GA ANGLE (5.9)	- PARTITION ANGLE
(BS)	- B421BR 4 X 2 X 1/2 X 16GA ANGLE (5.9)	- RAKE ANGLE
(BT)	- E4431BR/0 3 X 6 X 4 X 16GA STRUT (13.9)	- RIDGE STRUT

SHEETING SCHEDULE

(ML)	- 28GA M-LOC WALL PANEL
(PL)	- 28GA R-LOC WALL PANEL
(RL)	- 28GA PANEL-LOC WALL PANEL
(CL)	- 28GA R-PANEL WALL PANEL
(RR)	- 28GA PBR ROOF PANEL
(RW)	- 28GA PBR WALL PANEL

FASTENER SCHEDULE

(F1)	- CONC. EXP. ANCHOR (SIZE BY CUSTOMER)
(F2)	- 12 X 1 SD TEK (PLD)
(F3)	- 12 X 1 SD TEK (PND)
(F4)	- 12 X 2 SD TEK (PLD)
(F5)	- 12 X 1 1/4 WASHER TEK(OR ZAK)(PTD)
(F6)	- 12 X 1 1/4 WASHER TEK(OR ZAK)(PTD)(PLTD)
(F7)	- 12 X 1 1/4 WASHER TEK(OR ZAK)(PTD)
(F8)	- 14 X 7/8 WASHER TEK(OR ZAK)(PTD)
(F9)	- 14 X 7/8 WASHER TEK(OR ZAK)(PTD)(PLTD)
(F10)	- 14 X 7/8 WASHER TEK(OR ZAK)(PTD)
(F11)	- 1/8 POP RIVET
(F12)	- 12 X 1 1/4 WASHER TEK(OR ZAK)(PTD)
(F13)	- 12 X 1 1/4 WASHER TEK(OR ZAK)(PTD)
(F14)	- 14 X 7/8 WASHER TEK(OR ZAK)(PTD)
(F15)	- 14 X 7/8 WASHER TEK(OR ZAK)(PTD)(PLTD)
(F16)	- 1/8 POP RIVET

TRIM SCHEDULE

(BTR)	- 1" ROLL MASTIC
(CLN)	- R PANEL INSIDE FOAM CLOSURE
(CLOUT)	- R PANEL OUTSIDE FOAM CLOSURE
(GUT)	- GUTTER SEAL
(IC)	- R PANEL INSIDE CORNER TRIM
(ICD)	- R PANEL OUTSIDE CORNER TRIM
(ICW)	- DOOR CORNER MULLION
(IDK)	- EXTERIOR WALL PANEL LAP
(IDSS)	- DOWNSPOUT WITH KICK OUT
(IEF)	- EAVE FLASHING
(IFR)	- FORMED RIDGE CAP
(ITC)	- GUTTER HANGER STRAP
(ITD)	- POST HUNG GUTTER
(ITF)	- DOOR HEAD COVER
(ITG)	- DOOR HEAD TRIM
(ITH)	- HIGH EAVE TRIM

BASE TO SLAB CONNECTIONS

(S1)	- STRUCTURAL STEEL CONNECTIONS
(S2)	- PARTITION SHEETING
(S3)	- PARTITION ANGLE CONNECTIONS
(S4)	- EXTERIOR WALL SHEETING
(S5)	- ROOF SHEETING
(S6)	- EXTERIOR WALL PANEL LAP
(S7)	- ROOF PANEL LAP
(S8)	- INTERIOR TRIM LAP
(S9)	- EXTERIOR TRIM
(S10)	- INTERIOR TRIM
(S11)	- INTERIOR WALL SHEETING
(S12)	- INTERIOR TRIM DRILLER
(S13)	- INTERIOR WALL PANEL LAP
(S14)	- INTERIOR TRIM LAP
(S15)	- INTERIOR TRIM

INSIDE CORNER BOX

(ICB)	- INSIDE CORNER BOX
(ICD)	- LOW RIB INSIDE CORNER TRIM
(ICJ)	- DOOR JAMB TRIM
(ICK)	- DOOR JAMB CAP
(ICL)	- LOW RIB HEAD AND JAMB TRIM
(ICM)	- DOOR MULLION COVER TRIM
(ICN)	- LOW RIB OUTSIDE CORNER TRIM
(ICO)	- OUTSIDE CORNER BOX
(ICP)	- PEAK BOX
(ICQ)	- RAKE TRIM END CAP
(ICR)	- RAKE TRIM
(ICS)	- HALL TOP TRIM
(ICT)	- ROOF TIE IN TRIM
(ICU)	- ROOF STEP TRANSITION FLASHING
(ICV)	- 40Z TOUCH UP SPRAY PAINT

Central Storage Works
self-storage systems
By Central States Manufacturing

302 Jane Place, Lowell, AR 72745
(877)770-5206 fax (800)356-2971
www.centralstatesmfg.com

project- NEW STORAGE BUILDING PROJECT FOR:
NOT FOR CONSTRUCTION

customer- PRECONSTRUCTION REVIEW DRAWINGS

drawn date chkt date
TYP 01.01.04

draft-ink
p.o. box 14888 springfield, mo. 65814-0888
417.887.0101 fax.888.8064

sheet of
D06-06